


BRUHATH BANGALORE MAHANAGARA PALIKE

Rajarajeshwari Nagara Division

SCHEDULE-B

Name of Work : Providing and laying HDPE Water line in Mutyala Nagara Block-3 in J P Park, Ward No 17.

Agency			Sri K SHIVAKUMAR		
Sl No	Qty	Item Description	Unit	Rate	
				In Figures	In Words
1	2	3	4	5	6
1	2280.15	Earth work excavation for foundation of buildings, culverts, water supply, sanitary-lines and electrical conduits either in pits or in trenches 1.5m and above in width, in Hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications and as directed by the Engineer in charge.	Cum	244.00	Rupees Two Hundred Forty Four Only
2	2482.00	Providing and fixing to wall, ceiling and floor High Density Polyethylene Pipes 6.00 kgf/sq.cm working pressure 90mm outside diameter, compression type fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials, labour charges, HOM of equipments and testing excluding cost of fittings, complete as per specifications and as directed by the Engineer in charge.	Rmtr	536.00	Rupees Five Hundred Thirty Six Only
3	2602.50	Providing and fixing to wall, ceiling and floor High Density Polyethylene Pipes 10.00 kgf/sq.cm working pressure 25mm outside diameter, compression type fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials, labour charges, HOM of equipments and testing excluding cost of fittings, complete as per specifications and as directed by the Engineer in charge.	Rmtr	114.00	Rupees One Hundred Fourteen Only
4	416.40	Providing and fixing in trenches galvanised / mild steel tubes (medium grade) 20mm dia nominal bore with all fittings (earth work in trenches to be measured and paid for separately) including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications and as directed by the Engineer in charge.	Rmtr	211.00	Rupees Two Hundred Eleven Only
5	347.00	Providing and fixing 25mm dia nipple, complete as per specifications and as directed by the Engineer in charge.	No.	34.00	Rupees Thirty Four Only
6	694.00	Providing and fixing reducer elbow 25mm to 20mm complete as per specifications and as directed by the Engineer in charge.	No.	44.00	Rupees Forty Four Only
7	347.00	Providing and fixing 20mm dia nipple, complete as per specifications and as directed by the Engineer in charge.	No.	22.00	Rupees Twenty Two Only
8	694.00	Providing and fixing HDPE 90 x 32mm saddle with brass nuts and bolts including cost of all materials, labour charges, HOM of equipments and testing excluding cost of fittings, complete as per specifications and as directed by the Engineer in charge.	No.	375.00	Rupees Three Hundred Seventy Five Only
9	347.00	Providing and fixing 20mm dia union, complete as per specifications and as directed by the Engineer in charge.	No.	58.00	Rupees Fifty Eight Only
10	694.00	Providing and fixing 20mm dia hose collar, complete as per specifications and as directed by the Engineer in charge.	No.	28.00	Rupees Twenty Eight Only
11	694.00	Providing and fixing 20mm elbow, complete as per specifications and as directed by the Engineer in charge.	No.	19.00	Rupees Nineteen Only
12	694.00	Providing and fixing 20mm to 15mm reducer elbow, complete as per specifications and as directed by the Engineer in charge.	No.	24.00	Rupees Twenty Four Only
3	347.00	Providing and fixing 20mm NP bib cock complete as per specifications and as directed by the Engineer in charge.	No.	202.00	Rupees Two Hundred Two Only


Signature of Contractor


Executive Engineer
Rajarajeshwari Nagara Division
BBMP.


BRUHATH BANGALORE MAHANAGARA PALIKE

Rajarajeshwari Nagara Division

SCHEDULE-B

Name of Work : Providing and laying HDPE Water line in Mutyala Nagara Block-3 in J P Park, Ward No 17.

Agency			Sri K SHIVAKUMAR		
Sl No	Qty	Item Description	Unit	Rate	
				In Figures	In Words
1	2	3	4	5	6
1	2280.15	Earth work excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in Hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications and as directed by the Engineer in charge.	Cum	244.00	Rupees Two Hundred Forty Four Only
2	2482.00	Providing and fixing to wall, ceiling and floor High Density Polyethylene Pipes 6.00 kgf/sq.cm working pressure 90mm outside diameter, compression type fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials, labour charges, HOM of equipments and testing excluding cost of fittings, complete as per specifications and as directed by the Engineer in charge.	Rmtr	536.00	Rupees Five Hundred Thirty Six Only
3	2602.50	Providing and fixing to wall, ceiling and floor High Density Polyethylene Pipes 10.00 kgf/sq.cm working pressure 25mm outside diameter, compression type fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials, labour charges, HOM of equipments and testing excluding cost of fittings, complete as per specifications and as directed by the Engineer in charge.	Rmtr	114.00	Rupees One Hundred Fourteen Only
4	416.40	Providing and fixing in trenches galvanised / mild steel tubes (medium grade) 20mm dia nominal bore with all fittings (earth work in trenches to be measured and paid for separately) including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications and as directed by the Engineer in charge.	Rmtr	211.00	Rupees Two Hundred Eleven Only
5	347.00	Providing and fixing 25mm dia nipple, complete as per specifications and as directed by the Engineer in charge.	No.	34.00	Rupees Thirty Four Only
6	694.00	Providing and fixing reducer elbow 25mm to 20mm complete as per specifications and as directed by the Engineer in charge.	No.	44.00	Rupees Forty Four Only
7	347.00	Providing and fixing 20mm dia nipple, complete as per specifications and as directed by the Engineer in charge.	No.	22.00	Rupees Twenty Two Only
8	694.00	Providing and fixing HDPE 90 x 32mm saddle with brass nuts and bolts including cost of all materials, labour charges, HOM of equipments and testing excluding cost of fittings, complete as per specifications and as directed by the Engineer in charge.	No.	375.00	Rupees Three Hundred Seventy Five Only
9	347.00	Providing and fixing 20mm dia union, complete as per specifications and as directed by the Engineer in charge.	No.	58.00	Rupees Fifty Eight Only
10	694.00	Providing and fixing 20mm dia hose collar, complete as per specifications and as directed by the Engineer in charge.	No.	28.00	Rupees Twenty Eight Only
11	694.00	Providing and fixing 20mm elbow, complete as per specifications and as directed by the Engineer in charge.	No.	19.00	Rupees Nineteen Only
12	694.00	Providing and fixing 20mm to 15mm reducer elbow, complete as per specifications and as directed by the Engineer in charge.	No.	24.00	Rupees Twenty Four Only
3	347.00	Providing and fixing 20mm NP bib cock complete as per specifications and as directed by the Engineer in charge.	No.	202.00	Rupees Two Hundred Two Only


Signature of Contractor


Executive Engineer
Rajarajeshwari Nagara Division
BBMP